



Scale: 1 inch= 8 Ft.

Luminaire Schedule									
Symbol	Qty	Label	Arrangement	Lum. Lumens	LLF	Description	Lum. Watts	Arr. Watts	Total Watts
●	5	CPL1-18v	SINGLE	235	0.900	CPL1-18v	4.68	4.68	23.4

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
Copy_2 CalcPts 1	Illuminance	Lux	0.85	18.19	0.00	N.A.	N.A.
9 foot to top	Illuminance	Lux	8.84	18.19	2.74	3.23	6.64

Project Name: Perimeter Light Distribution - in LUX Details: CPL1-18v - 20 ft on center, (Every Other Post) Mounted fixture Top at 9 ft above grade.	Client: Date: 2/15/2016
	Photometrics: Joe Frey Filename: CL973-1953.AGI

CAST

PERIMETER

LED SECURITY LIGHTING SOLUTIONS

1120-A Goffle Road Hawthorne, NJ 07506 cast-lighting.com 973.423.2303

DISCLAIMER:
 These drawings are for conceptual use only and are not intended for construction. Values represented are an approximation generated from manufacturers photometric inhouse or independent lab tests with data supplied by lamp manufacturers.